

204

204

CHAINS

RESTORED CORNER FOR OREGON STATE BOARD OF FORESTRY

Section corner common to Sections 13 and 24,
T. 1S, R.9W, W.M., Tillamook County, Oregon.

ORIGINAL

Post, now missing, from which a:

22" Hemlock bears S89°W 59 lks.; now 30" Cedar uproot,
root hole in place, face rotted out, back cast of
scribe visible on overgrowth.

24" Hemlock bears N65°W 70 lks.; now missing, point
falls in slide area.

RESTORATION by W.E. Anderson, County Surveyor, April, 1932.

Set Fir limb, now missing from which a:

40" Fir bears S10°E 44.0 ft.; now 60" Scribes SC visible,
rest unexposed.

Rescribed original 30" Cedar bears S89°W 35.0 ft.;
(see original 22" Hemlock above.)

RESTORED

Set 1½" x 36" galvanized iron pipe with 3" bronze cap
marked "OREGON STATE BOARD OF FORESTRY T1S S13 S24 R9W
T1S R8W S18 1955 RE 2311," 35 inches in ground, and
from which a:

9" Hemlock bears N37°W 29.3 ft.; scribed T1S R9W S13
BT RE 2311.

Set 4"x3"x80" white Cedar post 1' NE of pipe.
Oregon State Board of Forestry metal location poster on
7" Hemlock S 2 W 8 ft.

Oregon State Board of Forestry metal location poster on
4"x4"x72" white Cedar post on E edge Wilson River
Highway 645'W.

Dated March 11, 1955.

Restored by Richard Morris under my direction.
Richard Morris, Engr. Aide



Present and witnessed by Lloyd Geraths

Book I