

CHAINS

Restored Corners: Page (111)

P. 1

Section Corner $\frac{4}{3}$ / $\frac{9}{10}$ T3N, R10W, W.M.

Original:

24" Hemlock
From which,

scribe Marks visible on NE Face.
Tree Broken off up 10ft. 3' Diam.

28" Hemlock N40°E 45 Lks snag 10' high Face Rotted.
24" Hemlock 377°E 21 " snag 8' high Face Rotted.
14" Hemlock 320°W 46 " Down No marks visible.
24" Hemlock N5°W 17 " Now 30" Face Rotted.

Restored Corner:

3/4" x 26" G.I. Pipe driven on East side of original
Tree. From which:

6" Hemlock 323°W 16 1/2 Ft scribed 59 BT.
10" " N70°E 26° Ft " 53 BT.

Quarter section Corner 9/10 T3N R10W, W.M.

Original:

Post 24" in ground Not Found.


From which:

12" Hemlock 338 1/2 E 19 Lks scribe Marks plainly visible
24" " 357 1/2 W 20 " Down, almost rotted away.

Restored Corner:

3" squared Cedar Post, From which:

6" Hemlock scribed 1/4 S E N14°W 6° Ft.
8" Hemlock " 1/4 S BT 36 1/2 E 5 1/2 Ft.



March 22, 1951.